


VICKERS PETRO.CO., INC.
Curtis No. 1.

SEC.6 T.22 R.13 W
CSL SW NW

DISCOVERY WELL

Total Depth. 3700'
Comn. 10-3-42 Comp. 10-22-42
Shot or Treated.
Contractor.
Issued. 11-7-42

County. Stafford



CASING:
10 $\frac{3}{4}$ " 320' Cem.
5 $\frac{1}{2}$ " 3693' Cem.

Elevation.

Production. Temp. Pot. Swb 25 B.
1 hr.

Figures Indicate Bottom of Formations.

sand	320
red beds	740
anhydrite	764
shale & shells	1360
salt	1575
shale & shells	1735
shale	1740
lime & shale	1775
lime	1885
shale & lime	2020
lime brkn	2110
lime	2275
lime & shale	2395
lime brkn	2615
lime & shale	2985
lime	3275
lime & shale	3366
lime	3607
shale, lime, chert	3629
chert	3646
shale green	3693
dolomite-showing oil	3700
Cored 3696-3700 rec 2 $\frac{1}{2}$ '	
dolomite showing oil	
Total Depth.	

Drilled Plug: 3250' oil in
3 hrs
Swbd 25 bbls oil one hr to
estb. temporary potential

Tops: Lansing	3366
Cherty Congl.	3620
Viola	3629
Simpson	3646
Arbuckle	3693