


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
 503 East Murdock, Wichita, Kansas

Company- THE VICKERS PETROLEUM CO., INC.
 Farm- Curtis "B" No. 3

SEC. 6 T. 22 R. 13W
 C W/2 W/2 NW NW
 240' fr. WL
 660' fr. NL NW $\frac{1}{4}$
 County Stafford
 KANSAS

Total Depth. 3610'
 Comm. 2-10-53 Comp. 3-3-53
 Shot or Treated.
 Contractor.
 Issued. 4-18-53



Elevation. 1917 RB

CASING:
 8 5/8" 343' cem w/250 sx.
 5 1/2" 3609' cem w/125 sx.

Production. Pot. flow 546 Bbls.
 1% wtr.

Figures indicate Bottom of Formations.

sand	300
shale, sand	315
red bed	343
red bed, sand	798
anhyd.	823
red bed, shale, shells	1285
shale, shells	1360
shale, salt	1550
shale, lime	1585
lime, shale	1720
lime, sand	1770
lime, shale	1815
lime, shale, sand	2035
lime	2135
lime, shale	2505
shale, lime	2820
lime, shale	3010
lime	3050
lime, shale	3155
lime	3244
black shale	3248
lime	3253
shale	3260
lime	3277
shale, sandy shale	3367
lime	3373
shale	3379
lime, little shale	3610
Total Depth	

Sample Tops	
Heebner	3244
Toronto	3260
Douglas	3277
Brown lime	3367
Lansing	3379

T. D. 3610 in Lansing Kansas City

Perforated 36 shots, 3405-3413
 Acidized with 2000 gals.