


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- VICKERS PETROLEUM & JAYHAWK DRLG.
Farm- Garvin **No. 1**

SEC. 8 **T.** 22 **R.** 13W
 SE SE NW

Total Depth. 3835
Comm. 9-22-52 **Comp.** 10-3-52
Shot or Treated.
Contractor.
Issued. 11-1-52

County Stafford
 KANSAS



CASING:
 8 5/8" 325 cem. w/250 sx.

Elevation. 1911 R.B.

Production. Dry

Figures Indicate Bottom of Formations.

sand & clay	295
red beds	420
red beds & sand	800
Anhyd.	825
red beds, shale &	
shells	950
shale, shells & salt	1415
lime & shale	1705
limebrkn	1800
lime & sand	1990
lime brkn	2005
sand & lime	2040
lime	2090
lime & shale	3035
lime	3165
lime & shale	3280
shale blk	3283
lime & shale	3299
lime	3319
shale	3409
lime	3414
shale & lime	3420
lime	3655
shale & lime	3673
shale & chert	3711
chert white	3754
shale & sand	3814
Dolo.	3835
Total Depth	

Tops: Sample	
Heebner	3280
Toronto	3299
Brown lime	3 409
Lansing	3420
Base Kansas City	3655
Congl. shale	3673
Viola chert	3711
Simpson shale	3754
Arbuckle	3814