


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company. PETROLEUM, INC.  
Farm- Soeken-Besthorn No. 2

SEC. 9 T. 22 R. 13W  
NW SE NW  
1650' FNL, 1650' FWL

Total Depth. 3800'  
Comm. 3-1-56 Comp. 3-10-56  
Shot or Treated.  
Contractor. Garvey Drlg. Co.  
Issued. 6-23-56

County Stafford  
KANSAS



Elevation. 1897' DF

Production. 25 BOPD

CASING:

8 5/8" 279' cem w/225 sx  
5 1/2" 3685' cem w/100 sx

Figures indicate Bottom of Formations.

soil & sand	210
sand & shells	253
blue shale	279
shale & shells	760
anhydrite	792
shale & shells	1505
lime & shale	3462
lime	3480
lime & shale	3520
lime	3612
lime & shale	3665
chert	3707
lime & shale	3800
Total Depth	3800 RTD

Tops:

Heebner	3239
Toronto	3258
Douglas	3274
Brown Lime	3366
Lansing	3385
Base Kansas City	3591
Cherty Conglomerate	3656
Viola	3662
Simpson Shale	3724
Simpson Sand	3741
Arbuckle	3780