


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- PETROLEUM, INC.  
Farm- Hahn "B" No. 1

SEC. 10 T. 22 R. 13W  
NE NE NE

Total Depth. 3738  
Comm. 7-26-52 Comp. 8-7-52  
Shot or Treated.  
Contractor. Garvey Drlg.  
Issued. 9-13-52

County Stafford  
KANSAS



**CASING:**  
8 5/8" 239' com. w/175 sx.

Elevation. 1887

Production. Dry

Figures Indicate Bottom of Formations.

surface soil	50
sand	190
clay	229
shale	239
red bed & sholls	730
Anhyd.	757
shale & sholls	1625
lime & shale	3086
lime	3263
lime & shale	3349
lime	3635
Viola chert	3672
chert	3684
sand & shale	3710
lime & shale	3719
lime	3738 RTD
Total Depth	

**Tops:**

Hoebner	3221
Brown lime	3348
Lansing	3367
Simpson	3680
Arbuckle	3733

D.S.T. # 1 3498-3557, open 1 hr., rec.  
30' mud, 130# BHP.  
D.S.T. # 2 3617-84, open 30 mins. rec.  
30' mud, 0# BHP  
D.S.T. # 3 3658-3710, open 45 mins.,  
rec. 23' mud, 42# BHP.  
D.S.T. # 4 3734 1/2-38, open 1 hr., rec. 30'  
watery mud, plus 540' wtr. BHP 1010#.