


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- LINDSLEY DRILLING CO.
 Farm- Drach "B" No. 1

SEC. 12 T. 22 R. 13W
 SW SW SW

Total Depth. 3810'
 Comm. 12-17-53 Comp. 12-30-53
 Shot or Treated.
 Contractor. Lindsley Drlg.
 Issued. 2-20-54

County Stafford
 KANSAS



CASING:
 8 5/8" 256.41' com w/250 sx

Elevation. 1899 FB

Production. Dry

Figures indicate Bottom of Formations.

sand, shale , shells	235
shale	265
red bed, shells	740
anhydrite	765
shale, shells	1230
salt	1300
salt, shale	1395
shale, shells	1610
lime, shale	2390
shale, shells	2795
lime, shale	3245
shale, lime strks	3350
lime	3674
shale, lime	3717
lime, chert	3757
Simpson	3793
shale, chert, lime	3810
Total Depth.	

Tops: R.B.	
Heebner	3243
Brown Lime	3377
Lansing	3394
Cherty Conglomerate	3638
Viola Chert	3698
Simpson	3756
Arbuckle	3791
Total Depth	3810

DRILL STEM TESTS:

#1 3793-3810', open 1 hr, weak blow for 18 min. Closed 20 min, BHP 12 #. Rec 15' Drlg mud. Plugged

DS @ 500' - 1°
 DS @ 1000' - OK
 DS @ 1500' - OK
 DS @ 2000' - OK
 DS @ 2500' - OK
 Lost circ @ 2750'
 Lost mud @ 3555'