

STANOLIND OIL & GAS CO.
Frank N. Schartz No. 2

SEC. 13 T. 22 R. 13W.
SWc NE
330' N of S.L. 330' E of W.L.

Total Depth. 3701 P.B. 3699
Comm. 5-10-38 Comp. 6-7-38
Shot or Treated. 2000 gal & 3000 gal.
Contractor.
Issued. 8-6-38

County Stafford.

Rotary 3676
Cable 3701



CASING.

103/4" 269'11" 6" 3672'

Elevation.

Production. Pot. 607 B.
3% wtr

Figures Indicate Bottom of Formations.

clay	18	Core No. 1 8/13' Rec.	
sand and shale	132	limestone tan oolitic. good	Acidizing Record.
sand gravel & shells	224	por. good spotted sat. show	3000 gal 6-6-38
shale blue	245	oil and gas	3480 Swabbed 70 bbls 3 hrs.
red bed	300	lime grey with thin grey	Core No. 10 3 1/2 / 4 Rec. 3697-
grey sdy shale	339	shale partings	3483 line slight sat. 3701
red bed and shells	724	lime	3583 Total Depth.
anhydrite	770	lime hard	3598 P.B. 3699
red and grey shale	810	conglomerate	3612 pumped 105 bbls in 4 hours.
shale and lime shells	940	chert & lime	3620
shale and lime	1287	shale and sand	3664 Top Lansing 3355
shale salt and shells	1507	chert	3665 Siliceous 3671-3701
lime and anhydrite	1707	Core No. 2 2 1/2 / 7' Rec.	
anhydrite and shale	1731	Rec. 2 1/2 dolomite tan fine	Swab 21.25 bbls in 4 hrs.
lime	1770	cryst. with thin green	no water June 1, 1938
lime broken & pyrite	1808	shale breaks, pyrite and	
broken lime	1823	cherty streaks, fair por.	
sdv shale and lime	1901	and fair sat.	3672
sdv lime	1931	Sample Analysis.	
shale and pyrite	1974	shale green sdy s.o.	3667
broken lime	2007	dolomite tan sugery in	
sdv lime and shale	2153	part with good sat.	3672
lime and pyrite	2158	Top Siliceous	
lime & strks of shale	2183	(by sample)	3667
broken lime shale	2247	Cable Tools	
sdv lime grey	2315	SLC	3672 = 3676
shale	2329	Top Siliceous Corr.	3671
lime broken	2339	Core No. 1 2/2' Rec.	
broken lime and shale	2514	Tan to grey lime light	
lime grey broken	2593	sh oil	3678
broken lime and shale	2817	Core No. 2 1/3 Rec.	
lime wh hard	2839	lime soft brown to grey	
lime strks of shale	2934	slight por. fair sat.	3681
shale	2955	Core No. 3 0/3 Rec.	
lime grey	3018	Brown soft sdy lime	3683
lime	3031	Swab test 21.25 bbls in	
shale & broken lime	3067	4 hours	
lime	3118	Core No. 4 0/3' Rec.	
shale strks of lime	3130	dolomite with streaks of	
lime white & brown	3154	green shale fair porosity	
shale	3160	fair sat.	3686
lime	3183	Core No. 5 0/2' Rec.	
sticky shale	3201	grey lime poor sat.	3688
lime & strks of shale	3235	Swabbed 34 bbls in 8 hrs.	
broken lime	3249	Acidizing Record.	
brown and blue shale with		2000 gal. 6-3-38	
streaks of lime	3301	Swabbed 60 bbls in 8 hours.	
shale and lime	3330	Core No. 6 0/3 Rec.	3688-3691
lime	3346	white hard lime no por.	
shale	3358	Core No. 7 1 1/2 / 2 Rec.	
lime	3364	white hard lime no por.	3691-3693
lime (show oil)	3379	no show oil.	
Top Lansing 3355		Core No. 8 2/2' Rec.	3693-3695
lime	3388	grey lime good sat. in	
lime white	3430	last foot.	
lime hard	3461	Swabbed 70 bbls in 8 hours.	
lime	3469	Core No. 9 0/2' Rec.	
Porous lime show oil	3470	lime good por. fair sat.	3695-3697