


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg. Wichita, Kansas

Company - FRANCO CENTRAL OIL CO.
Farm - Moon No. 3

SEC. 15 T. 22 R. 13W
SE SE NW

Total Depth. 3810
Comm. 10-5-48 Comp. 10-17-48
Shot or Treated Acid.
Contractor. Shawver-Graham, Inc.
Issued. 12-25-48

County. Stafford
KANSAS



Elevation. _____

Production. 30 BOFH

CASING:
8 5/8" 304' cem w/275 sx.
5 1/2" 3791' cem w/100 sx.

Figures Indicate Bottom of Formations.

sand, clay	70
shale, sand	80
sand	195
shale, shells	250
shale, shells	304
shale red and rock	750
shale, shells	1580
lime, shale	1635
shale	1662
lime	1758
shale, lime	1778
lime	1870
lime, shale	2040
lime	2170
lime, shale	2200
shale, shells	2580
lime, shale	2755
lime, brkn and shale	2800
shale, lime	2995
lime	3080
shale, lime	3162
shale	3177
shale, lime	3211
lime	3681
lime, chert	3739
lime	3755
lime, shale, sand	3790
lime RTD	3793
lime	3810
total depth	

Tops:

Heebner	3243
Brown Lime	3368
White Lime	3392
Viola	3689
Simpson	3735
Arbuckle	3789

Arb. prod. 6 BOFH after 1500
acid. L-W plug 3600' perf
30 shots 3512-20, acid 1000
test 30 BOFH.