

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - SINCLAIR-PRAIRIE OIL COMPANY
Farm - O. G. Soeken No. 1

SEC. 15 T. 22 R. 13W
SW SW NE

Total Depth. 3910
Comm. 7-11-47 Comp. 7-27-47
Shot or Treated.
Contractor. Kiowa Drilling Co.
Issued. 3-26-49

County. Stafford
KANSAS



CASING:
10 3/4" 295' csm w/250 sx.

Elevation. _____

Production. dry

Figures Indicate Bottom of Formations.

sand, clay	220
shale, shells	275
shale, shells, redrock	295
red rock, shale	775
anhydrite	800
shale	900
shale, shells	1350
salt, shale, shells	1450
shale, shells	1570
shale, lime	2590
shale, lime	2945
lime	3060
lime brkn	3130
lime	3310
lime, shale	3420
lime	3590
shale	3730
shale red	3740
conglomerate	3905
conglomerate ?	3910
Total depth	

Tops: SJ.

Lansing	3400
Conglomerate	3690

Fair porosity, no show in Topeka
Slight porosity, no show in L/K.C.
Slight porosity, slight oil stain
3577-78.
good porosity, 3588-95.