


WELL LOG BUREAU- KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- PETROLEUM INC.
Farm- Soeken "B" No. 1

SEC. 15 T. 22 R. 13W
SW SE NE

Total Depth. 3794
Comm. 8-18-52 Comp. 8-29-52
Shot or Treated.
Contractor. Garvey Drlg. Co.
Issued. 10-18-52

County Stafford
KANSAS



Elevation. 1894

Production. Pmp. 72 BO & unknown
amt. of wtr.

Figures Indicate Bottom of Formations.

CASING:

8 5/8" 290' cem. w/175 sx
5 1/2" 3787' cem. w/50 sx

surface soil	40
sand & gravel	240
red bed & shells	740
anhydrite	773
shale & shells	1500
shale & lime	3015
lime	3085
lime & shale	3192
lime	3245
lime & shale	3378
lime	3655
shale & lime	3669
chert	3707
viola chert	3733
simpson shale	3743
shale & lime	3790 RTD
shale & lime	3794
Total Depth	

Tops:

Heebner	3247
Brown Lime	3378
Lansing	3398
Conglomerate	3669
Simpson	3723
Arbuckle	3786

DST: #1 3420-70' open 45
mins. rec. 15' mud, 0# BHP.
DST: #2 3512-3543 open 30
mins. rec. 10' mud, 0# BHP
DST: #3 3545-90' open 45 mins.
rec. 20' mud 400# BHP
DST: #4 3787-90' open 1 hr.
rec. 250' gas 430' gassy oil
BHP 460#.