


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- **WELCH & OLSSON DRILLING CO., INC.**
 Farm- **Williams** No. **1**

SEC. **16** T. **22** R. **13W**
 SW SW SW

Total Depth. **3875**
 Comm. **1-24-54** Comp. **2-4-54**
 Shot or Treated.
 Contractor. **Welch & Olsson Drlg. Co., Inc.**
 Issued. **3-13-54**

County **Stafford**
KANSAS



CASING:
8 5/8" 300' cem. w/225 sx

Elevation. **1905 RB**

Production. **Dry**

Figures Indicate Bottom of Formations.

surface, soil & sand	110
sand	260
shale	440
shale & red bed	772
anhydrite	798
shale & shells	1650
shale & lime	1930
lime w/shale strks	2180
lime & shale	2335
shale & shells	2730
shale & lime	3303
lime	3305
shale	3404
lime	3702
conglomerate	3721
lime	3766
sand	3825
lime	3875
Total Depth	

Tops:	
Heebner	3275
Toronto	3295
Brown Lime	3404
Lansing-Kansas City	3424
Base-Kansas City	3646
Cherty Congl.	3699
Viola	3721
Simpson	3766
Arbuckle	3825