


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- BEARDMORE DRILLING COMPANY
Farm- Durham No. 1

SEC. 27 T. 22 R. 13W
SW SW NE

Total Depth. 3870'
Comm. 11-20-56 Comp. 11-29-56
Shot or Treated.
Contractor.
Issued. 12-22-56

County Stafford KANSAS



CASING:
8 5/8" @316' w/225 sx cem

Elevation. 1895' DF

Production. Dry

Figures Indicate Bottom of Formations.

cellar	5
sand	240
shale & shells	314
red bed	740
Anhydrite	765
shale	800
shale & shells	1550
shale & lime	3310
lime	3440
shale & lime	3500
lime	3783
shale	3810
shale & lime	3845
lime	3870 RTD
Total Depth	

TOPS	
Heebner	3274
Toronto	3295
Brown Lime	3409
Lansing	3427
Base/Kansas City	3640
Conglomerate	3708
Viola	3731
Simpson	3780
Arbuckle	3837

DRILL STEM TESTS:

DST #1 3547-3630 op. 1 hr., weak
blow 36 min. died, IBHP 610 in
30 min. FBHP 1100 in 30 min.
IF 0 FF 0, Hydrostatic 2110,
Rec. 65' mud.

DST #2 3706-3783 op. 1 hr., weak
blow, rec 58' mud. IBHP 0,
FBHP 960 in 30 min, IF 0, FF 0,
Temperature 102°, Hydrostatic 2160.

DST #3 3839-3845 op. 1 hr., fair blow,
IBHP 1240 in 30 min. FBHP 1240 in
30 min., IF 0, FF 80, Hydrostatic
2180, Temperature 102°, rec. 145'
sulphur water.