


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company PETROLEUM, INC.
Farm- Walls No. 1

SEC. 29 T. 22 R. 13W
SE NE SE

Total Depth. 3940
Comm. 6-29-52 Comp. 7-12-52
Shot or Treated.
Contractor. Garvey Drilling Co.
Issued. 10-25-52

County Stafford
KANSAS



CASING:
8 5/8" 273' c em. w/175 sx
5 1/2" 3939'

Elevation. 1934

Production. 505 BO & 8% wtr.

Figures indicate Bottom of Formations.

clay & surface sand	40
sand & gravel	250
shale & shells	273
shale, shells & red bed	796
anhydrite	829
shale & shells	1575
shale & lime	3437
lime	3789
conglomerate	3795
viola chert	3829
shale	3847
lime	3883
shale & lime	3895
lime	3940 RTD
Total Depth	

Tops:	
Heebner	3312
Brown Lime	3436
Lansing	3459
Congl.	3742
Viola	3773
Simpson	3829
Arbuckle	3889

DST: #1 3468-3522 open 1 hr.
rec. 600' gas & 120' slightly
oil and gas cut mud 200# BHP.

DST: #2 3572-86' open 1 hr.
rec. 2130' oil & 180' froggy
oil BHP 1400#.

DST: #3 3612-29' open 1 hr.
rec. 240' very heavily oil
cut mud, & 120' muddy oil,
1180# BHP

DST: #4 3636-76' open 1 hr.
rec. 1830' gassy oil, 1375#
BHP

DST: #5 3759-66' open 1 hr.
rec. 145' slightly oil and
gas cut mud, 1000# BHP.

DST: #6, 3777-3832 open 1 hr.
rec. 175' mud 1225# BHP

DST: #7 3872-78' open 30 mins.
rec. 5' mud 0# BHP

DST: #8 3890-95' open 1 hr.
rec. 5' mud, 1000# BHP

DST: #9 3892-3900' open 1 hr.
rec. 320' gassy oil & 40' wtr.
1275# BHP