


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- JACKSON DRILLING CORP.
Farm- Harris No. 1

SEC. 34 T. 22 R. 13W
SE SE NW

Total Depth. 3902 D.F.
Comm. 7-16-52 Comp. 7-30-52
Shot or Treated.
Contractor. Jackson Drlg.
Issued. 8-23-52

County Stafford
KANSAS



CASING:
8 5/8" 271' cem. w/200 sx.

Elevation. 1899 D.F.

Production. Dry

Figures Indicate Bottom of Formations.

clay & sand	70
water sand	150
shale & shells	195
sand	235
shale & shells	271
shale	375
shale & sand	700
shale & shells	760
anhyd.	790
shale & shells	1300
shale, shells & salt	1560
shale & shells	1700
lime & shale	1860
lime	2015
lime & shale	2325
shale & brkn lime	2515
shale & lime shells	2750
lime & shale	3488
lime	3685
shale & lime	3741
Viola lime	3775
lime & chert	3803
lime	3805
shale & sand	3853
Arbuckle lime	3902
Total Depth D.F.	

Tops: Corr. to Schlumberger

Hoebner	3287
Brown lime	3424
Lansing	3440
Base K.C.	3681
Viola	3747
Simpson	3807
Arbuckle	3857

D.S.T. 3458-88 op. 1 hr, rec. 20' mud
10' oil specked gas cut mud, no BHP.
3558-86, open 1 hr, rec. 60' oil &
gas cut mud, 210' gas, no BHP.
3590-3609, open 1 hr, weak blow 14 min.
rec. 38' mud trace spotted oil stain,
1100# BHP.
3858-69, open 1 hr, rec. 1560' sulphur
water, 1250# BHP.