


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- WESTGATE-GREENLAND OIL COMPANY
Farm- Harris No. 2

SEC. 34 T. 22 R. 13W
NE SW NW

Total Depth. 3882 RB
Comm. 10-24-52 Comp. 11-4-52
Shot or Treated.
Contractor. Westgate Drlg. Corp.
Issued. 12-6-52

County Stafford
KANSAS



CASING:

8 5/8" 296' cem. w/225 sx

Elevation. 1910 DF

Production. Dry

Figures Indicate Bottom of Formations.

sand & shale	150
shale	295
shale, sand & red bed	600
red bed	765
anhydrite	795
shale & shells	1340
shale & salt	1560
shale, shells	1680
lime w/shale	1780
lime	2065
shale & lime	2750
lime w/shale strks	2830
lime & shale	3254
lime	3300
lime & shale	3380
shale	3428
lime	3705
lime & shale	3723
lime & chert	3743
lime	3819
shale	3853
shale & sand	3857
arbuckle lime	3882 RB
Total Depth	

Tops:

Anhydrite	763
Heebner	3292
Brown Lime	3425
Lansing	3444
Base-Kansas City	3701
Viola	3742
Simpson	3803
Arbuckle	3855

DST: 3502-43' open 1 hr.
fair blow for the hour,
rec. 175' muddy salt water
BHP 990#.

DST: 3562-98' open 1 hr.
rec. 12' mud BHP 110#.

Run Schlumberger