


WELL LOG BUREAU---KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - J. A. DAVIS & J. H. CHILD  
Farm - Teichman No. 4

SEC. 12 T. 22 R. 13W  
SE SW NW SE

Total Depth. 3680  
Comm. 5-12-49 Comp. 5-24-49  
Shot or Treated.  
Contractor. Sterling Drilling Co.  
Issued. 7-2-49

County. Stafford  
KANSAS



Elevation. 1885 *end*

Production. 75 bbls.

CASING:

8 5/8" 320' cem w/200 sx.  
5 1/2" OD 3679' cem w/100 sx.

Figures Indicate Bottom of Formations.

clay, sand	220
shale, shells	320
shale, red bed	720
anhydrite	735
shale, red bed	1030
shale, shells	1210
salt, shale	1480
shale, lime	1865
lime	1990
lime, shale	3120
lime	3300
lime, shale	3342
lime	3582
Viola chert	3617
shale	3680
Total Depth	

Tops: (Sample)

Brown Lime	3318
Lansing K. C. limestone	3338
Cherty Conglomerate	3573
Viola Chert	3580
Simpson Shale	3615