

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


1-22-14W

Company- WESTGATE-GREENLAND OIL COMPANY
Farm- Wilson No. 1

SEC. 1 T. 22 R. 14W
NW NW SE

Total Depth. 3829
Comm. 10-9-52 Comp. 10-23-52
Shot or Treated.
Contractor. Westgate Drlg. Corp.
Issued. 11-22-52

County Stafford
KANSAS



CASING:

10 3/4" 313' cem. w/225 sx

Elevation. 1923 DE

Production. Dry

Figures Indicate Bottom of Formations.

sand, clay	210
shale & sand	280
shale & shells	313
red bed & sand	785
anhydrite	816
shale & shells	1650
lime & shale	1750
lime	2065
lime & shale	3345
shale	3395
lime	3645
shale & lime	3688
lime	3714
lime & chert	3747
viola lime	3748
simpson shale	3787
arbuckle lime	3829 RB
Total Depth	

Tops:

Anhydrite	783
Heebner	3268
Brown Lime	3392
Lansing	3404
Base-Kansas City	3636
Viola	3670
Simpson	3745
Arbuckle	3784

DST: 3403-52' 1 hr. rec. 75'
very slightly oil & gas cut
mud. 60' gas cut mud, 370# BHP.

DST: 3466-93' 1 hr. rec. 145'
watery mud, 1140# BHP

DST: 3561-3598' 1 hr. rec. 45'
muddy water, 1080# BHP weak
blow for 10 minutes, intermittent
blow rest of hr.

Schlumberger run