


Total Depth. 3806
Comm. 2-13-53 Comp. 2-27-53
Shot or Treated.
Contractor. Lohmann-Johson Drilling Co., Inc.
Issued. 5-30-53

County Stafford

1-22-14W



Elevation. 1929 RB

Production. Est. Phys. Pmp.

Figures Indicate Bottom of Formations. Pot. 197 BO, 197 BW

sand	300
red shale	340
red bed	780
anhydrite	825
shale & shells	1620
broken lime	1740
lime & shale	1965
broken lime	2135
lime	2220
shale	2523
lime & shale	2925
broken lime	2995
lime	3274
shale & lime	3444
lime	3522
lime & shale	3560
lime	3600
lime & shale	3642
lime & chert	3673
lime	3700
lime & shale	3739
lime & Heebner	3751
dolomite	3757
lime	3806
Total Depth	

SCHLUMBERGER TOPS:

Heebner	3275
Brown lime	3299
Lansing	3411
Viola	3658
Arbuckle	3744

Producing thru Arbuckle perforations
3752-71

DST #1: 3563-77, open 1 hr. rec. 15'
heavy oil cut mud, 20' slightly oil
cut mud, FP O# BHP 165#

DST #2: 3661-73, open 1 hr. rec. 8'
mud w/ few oil spots. FP O# BHP O#

DST #3: 3746-51, open 1 hr. wk. blow
for 10 min. rec. 8' mud w/ few oil
spots FP O# BHP O#

DST #4: 3747-57, open 1 hr. wk. blow
thruout test. rec. 95' heavy oil cut
mud. FP O# BHP 500#