

12-22-14W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- WESTGATE\*GREENLAND OIL CO.  
Farm- Williams "A" No. 1

SEC. 12 T. 22 R. 14W  
NW NV NW

Total Depth. 3796  
Comm. 1-28-52 Comp. 2-15-52  
Shot or Treated.  
Contractor. Jackson Drlg. Corp.  
Issued. 4-19-52

County Stafford  
KANSAS



CASING:

8 5/8" 332' cem. w/250 sx  
5 1/2" 3795' cem. w/100 sx

Elevation. 1932 DF.

Production. Temp. Prod. 25 BOPD

Figures Indicate Bottom of Formations.

sand w/clay strks	70
sand	155
sand & shale	315
shale & red bed	415
sand & shale	525
red bed & shale	630
red bed	802
anhydrite	829
shale & shells	1325
shale & shells w/salt	1545
shale w/salt	1620
shale & lime strks	1725
lime w/shale brks	1875
lime & shale	2010
lime	2155
lime & shale	3060
lime	3115
shale & silt	3140
lime & shale	3260
lime	3333
lime & shale	3416
lime	3623
lime & shale	3664
lime & chert	3675
chert	3696
simpson shale	3713
shale w/lime	3745
arbuckle	3796 RTD
Total Depth	

Tops:	
Anhydrite	802
Heebner	3272
Brown Lime	3395
Lansing	3408
Base KC	3630
Viola	3662
Simpson	3694
Arbuckle	3744

DST: 3445-82' 1 hr. rec. 90'  
GCM & 180' HOCM, 270# BHP  
DST: 3524-37, 1 hr. gas in  
35 min. rec. 150' froggy  
oil, 35' HO & GCM. 290# BHP  
DST: 3545-75' 1 1/4 hr. rec.  
180' O & GCM, 1000# BHP  
DST: 3743-58, 1 hr. 1255'  
gassy oil, 1380' gas 1400#  
BHP 600# FP. 25 gravity

Schlumberger run  
Perf 48 shots 3748-60 swab 8 BOPD  
natural no wtr swabbed 48 BO in  
6 hrs. 1400' off bottom