


14-22-14W

Company- STANOLIND OIL & GAS COMPANY
Farm- William McBride No. 1SEC. 14 T. 22 R. 14W
CE/2 NE NE
660' S. of NL 330' W. of EL NE/1Total Depth. 3805
Comm. 1-14-54 Comp. 1-27-54
Shot or Treated.
Contractor.
Issued. 3-13-54County Stafford
KANSASCASING:
8 5/8" 357' cem. w/300 sx

Elevation. 1934 RDB

Production. Dry

Figures Indicate Bottom of Formations.

sand, shale	358
shale, shells	815
anhydrite	855
shale, shells	1760
shale, lime	1915
lime	2470
shale, lime	3427
lime, no show	3725
sand, shale no show	3769
lime, slight oil specks	3805
Total Depth	

Tops:
Lansing 3427
Arbuckle 3769Total Depth
By Schlumberger 3802'
By Rotary Drill 3805'

Ran Schlumberger Elec. Log to T.D.

DST: #1 packer set at 3467-3488'
tool open 30 min. closed 15 min.
weak blow, rec. 15' rotary mud.
BHPSI 0DST: #2 packer set at 3551-3565'
tool open 30 min. closed 15 min.
weak blow for 8 mins. rec. 11'
rotary mud. BHPSI 1100 psiDST: #3 packer set at 3571-3601'
tool open 1 hr. closed 15 min.
weak blow 10 min. rec. 25' rotary
mud. slight oil show. BHPSI 0DST: #4 packer set at 3770-3775'
tool open 30 min. closed 30 min.
rec. 5' mud. BHPSI 0DST: #5 packer set at 3775-3785'
tool open 30 min. closed 30 mins.
rec. 375' mud w/oil specks BHPSI 0.

No show in sample 3785-3805'