

36-22-14W


WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company - SINCLAIR OIL & GAS CO.  
Farm - Shirley Beaver No. 1

SEC. 36 T. 22 R. 14W  
SE SE NW  
330' fr SL, 330' fr EL

Total Depth. 3935 PB 3906  
Comm. 9-22-49 Comp. 10-4-49  
Shot or Treated.  
Contractor. Acid.  
Issued. 12-17-49

County. Stafford  
KANSAS



Elevation. 1931 Ind.

Production. Pot. 377 bbls. oil  
no water.

CASING:  
8 5/8" 449' cem w/250 sx.  
5 1/2" 3928' cem w/175 sx. Drilled out to 3906

Figures Indicate Bottom of Formations.

sand, clay	450
red bed	835
anhydrite	860
shale shells	900
shale, salt, red bed	1144
shale, shells	1714
lime, shale	1844
lime, Ft. Riley	1929
lime, shale	2604
shale	2769
lime, shale	3631
lime	3764
lime cherty, shale	3789
lime, chert	3935
Total depth	PB 3906

Tops:

Kansas City	3457
Conglomerate	3749
Viola	3758
Simpson	3783
Arbuckle	3829

Good Porosity 3583-3590' fair  
stain and odor.

Remarks:  
Drilled cement plug to 3905' perforated  
Arb. 26 holes 3828-32'.  
Acid, 1000 gals, swbd 100 bbls fluid  
in 1 1/2 hrs, swabbing from 1600' 1/2" oil  
Set 5 1/2" drillable retainer about 25'  
above perforations. Squeezed 65 sx, cement  
Drilled out cement to 3906' which is  
completed P.B. TD. Perf. Arb. 24 holes  
3828-31' No show. Acid 1000 gals Swb  
6 to 8 gals water no oil pr hr. Acid again  
1000 gals. no show. Perf. 22 holes 3831-34'  
Acid 1000 gals, swbd to bottom and on 12  
hr test swbd 10 bbls oil, no water pr hr.  
State pot. Oct. 19, 1949, 377 bbls.