

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,

Wichita, Kansas


3-22-14W

Company- ALPINE OIL & ROYALTY CO., INC.
Farm- Cronwell No. 1
Cronwell

SEC. 3 T. 22 R. 14W
SE SE SW

Total Depth. 3910'
Comm. 10-17-58 Comp. 10-27-58
Shot or Treated.
Contractor. Quaker Drilling Co., Inc.
Issued. 11-15-58

County Stafford
KANSAS



Elevation. 1945 KB

Production. Dry

CASING:

8 5/8" 240' w/300 sx. cem.

Figures Indicate Bottom of Formations.

Surface Soil & sand	130
Very Hard sand	135
sandy shale	170
blue shale	240
shale & shells	300
red bed & shale	435
red bed, shale & sand	840
anhydrite	870
red bed & shale	1050
shale and shells	1485
shale	1700
lime and shale	1870
lime	2000
sandy lime and shale	2120
shale and lime	3385
sandy shale	3460
lime	3675
lime and shale	3730
lime, shale & chert	3790
lime	3795
lime and shale	3840
sand	3846
shale	3864
Dolomite and shale	3895
cherty lime	3910 RTD
Total Depth	

FORMATION TOPS

Anhydrite (Scout)	840
Heebner	3332
Brown Lime	3457
Lansing	3467
Viola	3754
Simpson	3814
Arbuckle	3864