


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
500 East Murdock, Wichita, Kansas

Company- REPUBLIC NATURAL GAS CO.
Farm- Bordewick No. 1

SEC. 1 T. 22 R. 14W
SW SW NW

Total Depth. 3772 PB 3720
Comm. 11-23-51 Comp. 2-7-52
Shot or Treated. Acid 500 gals
Contractor. Gabbert-Jones Drlg. Co.
Issued. 5-10-52

County Stafford
KANSAS



Elevation. 1933 K.B.

Production. I.P.P. 190 BO & NW

Figures indicate Bottom of Formations.

sand & shale	237
shale blue	246
shale & sand	695
shale	806
anhydrite	840
shale	990
shale & shells	1100
salt & shells	1200
shale & shells	1325
shale & lime	1460
shale, salt & shells	1680
shale & lime	1790
lime	2140
lime & shale	2230
lime	2295
shale & shells	2410
shale	2570
shale & shells	2695
shale & lime	2785
shale	2890
shale & lime	2990
lime brkn	3065
lime	3317
shale	3370
lime	3665
conglomerate	3680
cherty congl.	3717
lime & chert	3725
lime	3770 RTD
lime	3772
Total Depth	

Tops:	
Anhydrite	806
Hebner	3284
Lansing K.C.	3418
Viola	3697
Simpson	3721
Arbuckle	3762

PBTD 3720
Perforated 3473-3491 w/54
holes, 3 shots per foot.

Producing Formation: Lansing

5' from Braden Head up to zero.