

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - ALLAN ET AL
Farm - Wilson

No. 3

SEC. 1
NE SE SE

T. 22

R. 14 W

Deepening Record

Total Depth. 4025'

Comm. 12-16-46

Comp. 12-31-46

County.

Stafford

Shot or Treated.

Contractor. Tom Allan

Issued. 1-11-47

KANSAS



Elevation. _____

Production. Dry

CASING:

8 5/8" 368' Cem. w/175 sx.
(See deepening record below)

Figures Indicate Bottom of Formations.

surface sand	0-275	hrd cherty xlyn	
red beds	368	dolomite	3840
Cemented 8 5/8" csg.			
red beds	776	no oil saturation	
wht gyp & anhydrite	800		
red beds	1100		
shale	1300		
salt & shale	1600		
shale & shells	1780		
dolomite cherty	1805		
shale & shells	1845		
porous cherty			
dolomite	1875		
shale gy & red	1902		
cherty lime	1910		
partly porous lime	2000		
shale	2006		
cherty fusilinid			
lime	2036		
shale	2060		
porous lime	2076		
limes & shales	2440		
shale & shells	2960		
lime & shale brks	3300		
shale	3380		
lime brwn	3385		
shale	3394		
wht. lime	3405		
shale	3415		
lime	3425		
sft porous lime	3430		
lime & shale	3438		
sft porous lime	3442		
lime & shale	3467		
sft porous lime	3471		
lime	3482		
oolitic lime	3490		
lime	3525		
sft porous lime	3530		
lime	3560		
sli. porous lime	3570		
shale & lime	3594		
shale	3605		
wh xlyn lime	3615		
shale	3623		
lime dense buff	3629		
shale	3640		
red shale conglom-			
erate	3676		
weathered & vari-			
color chert	3697		
d shale conglomerate			
& little weathered			
chert	3769		
weathered dolomite			
& chert	3800		
red & green shale &			
little weathered			
chert	3833		

Formations:

Top Anhydrite	776
Base Florence Flint	2036
Top Iatan	3380
Top Lansing	3394
Top Penn. Conglom-	
erate	3640
Top Ordovician	
Conglomerate	3769
Top Arbuckle	3833

Deepening Record :

January 1, 1947 - January 3, 1947

3840-4025' Hrd cherty xlyn dolomite

ran 5 1/2" casing to 3855' and cemented
over special Baker Shoe w/50 sx
cement.

4025' T. D. - Shut down for water
disposal permit.