


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- WESTGATE-GREENLAND OIL CO.
Farm- Keenan No. 1

SEC. 2 T. 22 R. 14W
SW SW NE

Total Depth. 3786 RB
Comm. 7-22-51 Comp. 8-8-51
Shot or Treated.
Contractor. Jackson Drlg.
Issued. 10-6-51

County Stafford
KANSAS



CASING:

10 3/4" 314' cem w/225 sxs.
7" 3620' cem w/100 sxs.

Elevation. 1935 DF

Production. Swb. 120 bbls.
in 8 hrs.

Figures Indicate Bottom of Formations.

sand	130
sand, clay	210
shale	295
shells	314
shale, shells	340
red bed, shale	460
red bed, sand	520
red bed	813
anhydrite	845
shale, shells	1700
lime, shale	2150
shale	2220
shale, lime	2540
shalc	2755
lime, shale	3075
lime	3145
shale, lime	3396
lime	3660
lime, shale	3702
lime	3734
lime, shale	3776
Arbuckle	3786 RB
Total depth	

Tops: DF	
Anhydrite	813
Heebner	3290
Brown lime	3414
Lansing	3425
Viola	3686
Simpson	3724
Arbuckle	3774

DF measurements

DST 3487-3501, open 1 hr., rec.
80' salt wtr. & mud BHP 450#
DST 3546-58 gas in 25 mins,
open 1 hr., rec. 360' mud cut oil
(froggy oil) BHP 1270#.
DST 3562-94, open 1 hr., rec.
60' salt wtr. BHP 975#
Perf. 72 holes 3546-58, swab
1 3/4 BOPH for 8 hrs. 500 GA
built up maximum pressure of
400#, swab 1500' down in hole,
15 BOPH, flows when swab is pulled.