


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SUNRAY OIL COMPANY
Farm- Keenan No. 2

SEC. 2 T. 22 R. 14W
NE SE SW

Total Depth. 3810
Comm. 9-12-51 Comp. 9-24-51
Shot or Treated.
Contractor. Jackson Dr'lg Corp.
Issued. 11-24-51

County Stafford
KANSAS



Elevation. 1935 D.F.

CASING:
8 5/8" 340' cem w/250 sx.
5 1/2" 3810' cem w/125 sx.

Production. Pot. 193 BOPD / 3%
wtr.

Figures Indicate Bottom of Formations.

sand	150
sand, shale	240
shale, shells	340
shale, red bed	520
shale	820
anhydrite	855
shale, shells	1815
shale, lime	1880
lime	2125
lime, shale	2810
lime	2975
lime, shale	3418
lime	3643
lime, shale	3678
lime cherty	3701
viola	3722
shale	3772
lime arbuckle	3810
Total Depth	Rotary

Tops:
Lansing 3418
Viola 3683
Simpson 3720
Arbuckle 3772

DST: 3478-97, open 40 min,
rec. 205' heavy oil & gas
cut mud, 90' clean oil,
5' water

DST: 3533-50, open 20 min.
rec. 180' heavy oil & gas
cut mud, 60' free oil, gas
in 11 mins. BHP 1060#.

DST: 3773-3778, open 1 hr.
rec. 105' heavy oil, BHP 990#.

RTD; 40/3543-52; 10 gal. oil 2
gal wtr 6 hrs; 18 gal oph 7 hrs
no wtr; 2500 A; 18 boph 7 hrs no wtr;
Pot. 193 bopd / 3% wtr.