


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- **WESTGATE-GREENLAND OIL CO.**
 Farm- **Keenan** No. **2**

SEC. **2** T. **22** R. **14W**
 SW SE NE

Total Depth. **3805**
 Comm. **9-27-51** Comp. **10-18-51**
 Shot or Treated.
 Contractor. **Jackson Drlg. Corp.**
 Issued. **2-23-52**

County **Stafford**
KANSAS



CASING:

10 3/4" 329' cem. w/225 sx
 6 5/8" 3607' cem. w/75 sx

Elevation. **1935 DF**

Production. **400 bbls.**

Figures Indicate Bottom of Formations.

sand	190
shale, sand	250
shale, shells	365
red bed, shale	670
red bed	812
anhydrite	850
shale & shells	1300
shale	1600
lime & shale	1758
lime	1778
lime & shale	2210
shale	2365
lime & shale	2680
shale	2785
lime & shale	3425
lime brown	3429
lime lansing	3646
lime & shale	3695
viola	3736
shale	3781
arbuckle lime	3805 RB
Total Depth	

Tops:

Heebner	3293
Brown Line	3417
Lansing	3428
Base-Kansas City	3660
Viola	3695
Simpson Shale	3735
Arbuckle	3779

DST: 3491-3504, open 1
 hr, rec. 210' very sl.
 oil cut salt water, BHP
 940#.

DST: 3547-58, open 1 hr,
 gas in 23 min, 30' free
 oil, 300' mud cut oil,
 900# BHP

DST: 3608-19, open 1 hr.
 rec. 15' oil cut mud, no
 BHP

DST: 3777-92 open 1 hr. rec.
 25' mud, BHP 370#.

Perf. 69 shots 3542-56', 1000
 GA, swb 110 BO in 3 hrs.