


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- WESTGATE—GREENLAND OIL CO.
Farm- Keenan No. 3

SEC. 2 T. 22 R. 14W
SE SE NE

Total Depth. 3810
Comm. 5-19-52 Comp. 6-7-52
Shower tested.
Contractor. Jackson Drilg. Corp.
Issued. 8-9-52

County Stafford
KANSAS



Elevation. ~~1937~~ DE

Production. Temp. 25 BOPD

CASING:

10 3/4" 345' cem. w/235 sx
7" 3809' cem. w/150 sx

Figures Indicate Bottom of Formations.

sand & clay	240
sand & shale	335
shale	400
red bed & shale	635
shale & sand	785
shale & red bed	814
anhydrite	850
shale & red bed	1110
shale & shells	1700
shale & lime	1736
shale	1850
lime	1981
lime & shale	2152
lime	2200
shale	2257
shale & shells	2447
shale & lime brown	2618
lime & shale	3130
lime	3195
shale	3225
lime & shale	3265
lime	3295
lime & shale	3340
shale	3420
lime	3664
shale & lime	3692
cherty lime	3725
lime & shale	3770
lime, arbuckle	3810 RB
Total Depth	

Tops:

Anhydrite	812
Hoebner	3292
Brown Lime	3419
Lansing	3430
Base-K. C.	3664
Viola	3690
Simpson	3726
Arbuckle	3768

DST: 3496-3505', 1 hr. 30'
mud, 700# BHP
DST: 3507-27' 1 hr. 15'
mud 900# BHP
DST: 3545-58' 1 hr. 110'
froggy oil, 40' oil cut mud,
900# BHP
DST: 3564-95' 1 hr. 155' muddy
SW, 1050# BHP
DST: 3770-83' 1 hr. 70' heavily
oil cut mud 635# BHP

Schlumberger Run
Perf 78 shots 3770-3788, 1000 GA,
swabbed 6 BOPH for 10 hrs.