

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas

Company- SUNRAY OIL CORP.
Farm- Keonan No. 4

SEC. 2 T. 22 R. 14W
SW SE SW

Total Depth. 3791
Comm. 12-29-51 Comp. 1-11-52
Shot or Treated.
Contractor. Anschutz Drlg.
Issued. 3-8-52

County Stafford
KANSAS



CASING:

8" 344'
5" 3787'

Elevation. 1935

Production. 185 bbls. & no wtr.

Figures Indicate Bottom of Formations.

clay & sand	240
shale & shells	550
shale red	818
anhyd.	859
shale & shells	1125
salt	1230
shale	1320
shale & shells	1635
shale & lime	1855
lime	2085
lime & shale	2175
shale	2300
lime & shale	2535
shale	2695
shale & lime	2885
lime	3230
lime & shale	3375
lime	3690
lime & chert	3735
lime & shale	3780
li e	3791 RTD
Total Depth	

Tops:			
Heebner	3295	Simp.	3730
latan	3419	Arb.	3786
Lansing	3429		
BKC...	3660		
Congl	3689		
Vibla	3696		

D.S.T. 3545-58 op. 1 hr. rec 120' oil
plus 56' OCM BHP 800#
3787-91 op 1 hr. rec 15' oily mud
BHP 248 CO 3753 19 holes 3547-53 test
3/4 BOPH fro 6 hr. 2000 acid sw. 20 BOPH
for 4 hrs.