


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- WESTGATE GREENLAND OIL CO!
Farm- Wetig No. 2

SEC. 2 T. 22 R. 14W
SE NW SE

Total Depth. 3775 RB
Comm. 8-4-51 Comp. 8-22-51
Shot or Treated.
Contractor. Jackson Drlg. Co.
Issued. 10-20-51

County Stafford
KANSAS



Elevation. 1937 DF

Production. Temp. Prod. 25 bbls.

Figures Indicate Bottom of Formations.

sand	170
shale & sand	255
shale & shells	339
shale & red bed	560
red bed & sand	620
red bed & shale	730
red bed	815
anhydrite	845
shale & red bed	1160
shale & shells	1360
shale	1740
shale & lime	1950
lime	2045
lime & shale	2620
shale	2765
lime & shale	3095
shale & lime	3290
shale	3355
heebner shale	3411
brown lime	3421
lansing lime	3439
lime	3638
lime & shale	3676
chert	3701
viola	3720
simpson	3747
shale	3756
arbuckle	3775
Total Depth RB	

Tops:	
Anhydrite	813
Heebner	3270
Brown Lime	3408
Lansing	3416
Base Kansas City	3648
conglomerate	3668
Viola	3678
Simpson	3717
Arbuckle	3755

DST: 3483-96, open 50 min.
gas to surface in 35 mins.
rec. 120' oil, 120' oil cut
mud, BHP 1000#.
3535-46, open 1 hr, gas in
16 min. rec. 1570' gassy oil,
60' oil cut mud, 60' muddy
water, BHP 1030#.
3555-88, open 1 hr. rec. 65'
oil cut mud.
3756-73, open 1 hr, rec. 420'
gas 280' oil, 50' muddy water
BHP 700#.

Perf. 47 holes 3756-67½, 1000
GA., filled up 1000' in 3 hrs.
swabbed approx. 8 BOPH. 90 BO in
12 hr. test.