


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company. WESTGATE-GREENLAND Oil Company  
Farm. Wetig No. 3

SEC. 2 T. 22 R. 14W  
NW SW SE

Total Depth. 3820 RB  
Comm. 8-19-51 Comp. 9-8-51  
Shot or Treated.  
Contractor. Jackson Drilg Corp.  
Issued. 11-24-51

County Stafford  
KANSAS



CASING:

8 5/8" 343' cem w/225 sx.  
5 1/2" 3820' cem w/100 sx.

Elevation. 1934 DF

Production. 366 BOPD  $\neq$  4% water

Figures indicate Bottom of Formations.

sand	95
sand w/shale	200
shale w/sand strks	325
shale	344
red bed w/sand strks	810
anhydrite	838
shale, shells	1315
shale, salt	1635
lime w.shale	1680
lime	1790
lime, shale	2160
lime	2210
shale, lime	2765
lime	2795
lime, shale	2910
lime	2930
lime w/shale	3065
lime	3190
shale, lime	3418
lime brown	3424
lansing	3440
lime	3505
lime K.C.	3523
lime	3658
conglomerate	3678
lime, shale	3692
lime viola	3725
shale simpson	3727
shale, lime	3758
shale	3760
arbuckle	3820
Total Depth RB	

Tops:  
Heebner 3290  
Brown Lime 3415  
Lansing 3426  
Base Kansas City 3656  
Viola 3689  
Simpson 3722  
Arbuckle 3758

DST: 3491-3503, op. 1/2 hr,  
blow 10 min., rec.  
30' mud, BHP 910#.  
DST: 3543-57, op. 1 hr,  
rec. 600' gas, 60' oil cut  
mud. BHP 180#.  
DST: 3563-94, op. 1/2 hr, rec.  
6' mud, BHP 320#.  
DST: 3603-23, op. 1/2 hr, rec.  
30' muddy salt water.  
BHP 1140#.  
DST: 3760-72, op. 1 hr, rec.  
37' mud, no BHP

perf. 116 shots 3757-97, show  
oil, no water 1000 GA,  
water PB 3580.  
perf. 66 shots 3539-63, 1000 GA,  
swab 100 BO in 3 hrs.