


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Muddock, Wichita, Kansas

Company- WESTGATE-GREENLAND OIL COMPANY
Farm- Wetig No. 4

SEC. 2 T. 22 R. 14W
NW NE SE

Total Depth. 3805 RB
Comm. 9-2-51 Comp. 9-22-51
Shot or Treated.
Contractor. Jackson Drilg Corp.
Issued. 11-24-51

County Stafford
KANSAS



Elevation. 1935

Production. Pot. 1603 bbls / 8%
water

CASING:

8 5/8" 339' cem w/225 sx
5 1/2" 3802' DF cem w/ 75 sx

Figures Indicate Bottom of Formations.

sand	105
sand w/shale streaks	200
shale	340
shale, red bed	570
red bed	812
anhydrite	841
shale, shells	1310
shale, salt	1615
lime w/shale brks	1820
lime	1955
lime, shale	2075
lime	2090
lime, shale	3080
lime	3185
S. Lt and shale	3212
lime, shale	3430
lime	3647
lime, shale	3676
lime viola	3686
chert, cherty lime	3710
shale	3733
shale, lime	3755
arbuckle	3805 RTD
Total Depth RB	

Tops:
Heebner 3283
Brown Lime 3406
Lansing 3417
B/Kansas City 3649
Viola 3670
Simpson 3708
Arbuckle 3752

DST: 3476-92, open 1 hr, gas
to surface in 10 min. rec.
1350' oil, 930# BHP
DST: 3533-46, open 1 hr, gas to
surface in 9 min., rec. 2040'
oil, BHP 1000#.
DST: 3752-74, open 1 hr, rec. 630'
oil, 60' HOCM with BHP 530#.
Perf: 48 shots 3533-48, 500' oil
in hole, 2000 GA, flow 50 BOPH
on 2 1/2 hr test.