


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
502 East Murdock, Wichita, Kansas

Company: WESTGATE-GREENLAND OIL CO.
Farm: Metig No. 5

SEC. 2 T. 22 R. 14W
NW. SE SE

Total Depth. 4165 R.B.
Comm. 9-15-51 Comp. 9-29-51
Shot or Treated.
Contractor. Jackson Drlg.
Issued. 3-8-52

County Stafford
KANSAS



Elevation. 1938 D.F.

Production. S.W.

CASING:

8 5/8" 334' cem. w/225 sx.
5 1/2" 3910 cem. w/125 sx.

Figures indicate Bottom of Formations.

sand	130
shale w/sand strks	320
shale	345
shale & red bed	813
anhyd.	845
shale	860
shale & shells	1320
shale & salt	1620
shale & lime	1695
lime	1960
shale	1980
shale w/lime strks	2050
lime w/shale	2085
lime	2160
shale	2170
lime & shale	3175
lime	3242
lime & shale	3440
lime	3680
shale & lime w/chert	3814
Arb. lime	3920
rb. w/chert	4061
lime w/shale &	
chert	4085
Arb. w/chert	4117
lime & chert	4165 R.B.
Total Depth	

Tops:	
Anhyd.	813
Heebner	3303
Brown lime	3428
Lansing	3440
Viola	3706
Simpson	3746
Arb.	3804

U.S.T. 3595-26 open 1 hr, rec. 35' muddy
salt wtr. 1030# BHP
3502-17 open 1 hr. rec. 65' mud
s wtr BHP 1085#
3557-69 open 1 hr. rec. 5' mud no BHP

Run lateral and micro log to bottom,
Gamma Ray to 70' in Arb.
Well to be used as S.W.