

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. D. R. LAUCK OIL CO., INC.
Farm- Long No. 2

SEC. 5 T. 22 R. 14W
SE SW SE

Total Depth. 3895

Comm. 8-18-55


Comp. 8-30-55

Shot or Treated.

Contractor.

Issued. 10-8-55

County Stafford
KANSAS



8 5/8 CASING:
228' w/ 200 sx cmt.

Elevation. 1948 DF

Production. Dry

Figures indicate Bottom of Formations

sand	195
shale & shells	345
sand	460
red bed & shells	780
shale & red bed	876
anhydrite	905
shale & shells	1690
lime & shale	2530
shale & shells	2968
lime & shale	3320
lime	3370
shale	3384
lime & shale	3465
lime	3765
cherty lime	3830
lime & shale	3855
sand & shale	3865
conglomerate	3880
Arbuckle	3895
Total Depth	

TOPS:

Anhydrite	876
Heebner	3345
Brown lime	3465
Lansing	3473
Conglomerate	3767
Viola	3779
Simpson	3830
Arbuckle	3881

DST #1: 3847-65, open 30 min. wk. bl.
6 min. rec 10' mud. BHP 0#/15 min.

DST #2: 3881-84, open 30 min. wk. bl.
10 min. rec. 10' mud, BHP 810#/20 min.

DST #3: 3883-87, open 30 min. wk. bl.
8 min. rec. 15' mud, BHP 720#/20 min.

DST #4: 3887-95, open 1 hr. fair to
wk. bl. 45 min. rec. 70' thin watery
mud, BHP 1050#/20 min.