


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. NATURAL GAS & OIL CORPORATION
Farm. E. Morrison No. 2

SEC. 5 T. 22 R. 14W
SE NW SW

Total Depth. 3877
Comm. 12-9-54 Comp. 12-20-54
Shot or Treated.
Contractor. Graham-Messman-Rinehart Drlg.
Issued. 3-26-55

County Stafford
KANSAS



CASING:

10 3/4" 290' cem. w/275 sx
5 1/2" 3875' cem. w/125 sx

Elevation. 1958 KB

Production. 99 bbls. oil

Figures indicate Bottom of Formations.

sand & clay	243
shale	290
redbed	340
sand	425
redbed	470
sand	510
redbed	886
Anhydrite	910
shale & shells	1260
shale	1535
shale & shells	1662
lime & shale	3285
lime	3405
lime & shale	3455
lime	3490
lime & shale	3570
lime	3754
cherty Viola	3807
Simpson shale	3864
Arbuckle	3877
Total depth	

Sample Tops:	
Heebner	3335
Brown lime	3455
Lansing	3464
Viola	3754
Simpson shale	3807
Arbuckle	3864