

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas

Company - WESTGATE-GREENLAND OIL CO.
Farm - Russell No. 1

SEC. 6 T. 22 R. 14W
SE SE NW

Total Depth. 3895

Comm. 6-19-51

Comp. 7-4-51

Shot or Treated.

Contractor. Jackson Drlg. Corp.

Issued. 7-28-51

County. Stafford

KANSAS



CASING:

8 5/8" 258' cem. w/200 sx.

Elevation. 1961 D.F.

Production. Dry

Figures Indicate Bottom of Formations.

sand	215
shale & shells	258
shale	290
sand & red bed	330
red bed	895
anhyd.	925
shale, salt & shells	1190
shale & shells	1475
shale & red bed	1600
shale	1700
lime & shale	1715
lime	2030
lime & shale	3364
shale	3400
shale & lime	3470
lime	3688
shale & lime	3760
congl.	3796
chert	3826
congl.	3889
Arb.	3895
Total Depth	

Tops:

Anhyd.	895
Brown lime	3456
Lansing	3476
Congl.	3757
Viola	3767
Arb.	3879

D.S.T. 3588-3596, rec 60' HOCH & 150' salt
wtr-open 1 1/2 hrs.

D.S.T. 3612-33, open 1 hr, rec. 120' HOCH.

D.S.T. 3874-95, open 45 min., rec. 2930'
salt wtr.