

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- BIRMINGHAM-BARTLETT DRILLING CO.
Farm- Smith "A" No. 1

SEC. 7 T. 22 R. 14W
SW NE SW

Total Depth. 3884

Comm. 1-7-53


Comp. 1-21-53

Shot or Treated.

Contractor. Birmingham-Bartlett Drilling Co.

Issued. 6-13-53

County Stafford
KANSAS



Elevation. 1963 RB

Production. Dry

CASING:

8 5/8 set at 293' w/ 325 sx cement
5 1/2 set at 3879' w/ 125 sx cement

Figures Indicate Bottom of Formations.

sand	100
shale	160
sand	220
shale & shells	293
red bed	400
sand	890
anhydrite	900
shale & shells	1460
shale & lime	1700
broken lime	1735
lime & shale	1900
broken lime	2185
lime & shale	2283
broken lime & shale	2435
shale & shells	2705
shale & lime streaks	2860
shale & lime	3160
lime	3390
shale	3420
shale & lime	3495
lime	3770
conglomerate	3785
lime & chert	3820
shale & lime	3874
shale	3877
Arbuckle	3884
Total Depth	

TOPS:

Anhydrite	890
Brown lime	3466
Lansing	3476
Conglomerate	3766
Viola	3775
Simpson	3815
Arbuckle	3877

Drilled plug & deepened 2 ' tested
60 gal SW w/ SO. Drilled deeper to
3884'. Tested 3 bbls SWPH. Plugged
back to Viola & Perf. w/ 87 shots
3768-3803 plus 500 gal acid. Swbd.
9 BOPH for 12 hrs. 100' of bottom.
Put on pump. Production later dropped
to 0

Plugged back to KC & perf. w/ 51 shots
3689-3702. Swbd 31 BO & 10 BW in 2 hrs.
Set new plug & squeezed above perf.
Re-perf. 3676-3702

Pumping test 24 hrs. produced 60 BO
& 22 water.