


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- PETROLEUM, INC.
Farm- Strobol "C" No. 1

SEC. 8 T. 22 R. 14W
SE NE NW

Total Depth. 3893
Comm. 7-13-52 Comp. 7-24-52
Shot or Treated.
Contractor. Garvey Drlg.
Issued. 9-13-52

County Stafford
KANSAS



Elevation. 1954

Production 94 bbls. & no wtr.

Figures Indicate Bottom of Formations.

CASING:
8 5/8" 225 com. w/175 sx.
5 1/2" 3889 com. w/75 sx.

surface clay	40
sand	207
shale	296
red bed	630
red bed & shales	878
anhyd.	907
shale & shells	1270
lime & shale	3174
lime	3396
lime & shale	3490
lime	3781
Viola	3830
shale	3837
shale, sand	3861
shale & lime	3885
lime	3893 RTD
Total Depth	

Tops:
Hoobner 3339
Brown lime 3468
Lansing 3479
Congl. 3773
Viola 3778
Simpson 3831
Arbuckle 3887

D.S.T. #1 3595-3610, open 30 mins ,
rec. 8' mud, 0 # BHP.
D.S.T. # 2 3854-61 open 1 hr., rec.
305' free oil / 50' oil cut mud, 14.75 #
BHP
D.S.T. # 3 3888-93, open 1 hr., rec. watery
mud, 300 # BHP.