

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- PETROLEUM, INC.

Farm- Unruh

No. 2

SEC. 8

T. 22

R. 14W

NW NW SE

Total Depth. 3925'

Comm. 7-12-58

Comp. 7-22-58


Shot or Treated.

Contractor. Garvey Drilg. Co.

Issued. 5-16-59

County Stafford

KANSAS



Elevation. 1956' DF

Production. 15 BOPD

CASING:

8 5/8" 254' cem w/150 sx.

5 1/2" 3923' cem w/75 sx.

Figures Indicate Bottom of Formations.

sand	120
sand & clay	255
sand & red bed	490
red bed & shale	875
Anhydrite	905
shale & shells	1220
shale, shells & lime	1650
lime & shale	2400
shale & lime	2585
lime & shale	2900
shale & lime	3030
lime & shale	3135
lime	3334
lime & shale	3414
lime	3775
cherty lime	3810
chert	3823
lime & shale	3895
Arbuckle lime	3925
Total Depth	

TOPS: SCOUT

Anhydrite	875
Heebner	3348
Toronto	3370
Brown Lime	3471
Lansing	3485
Cherty Conglomerate	3774
Viola	3783
Simpson Shale	3819
Simpson Sand	3857
Arbuckle	3884