

24-22-16W
SW SW SW

NOV 10 1972

COMPANY **Hershberger Explorations, Inc.**

SEC. 24 T. 22S. R. 16W
LOC. SW SW SW


FARM **Doll** NO. **1**

API # 15-145-20, 265

TOTAL DEPTH **4,055'**
COMM. **September 18, 1972** COMP. **September 27, 1972**

COUNTY **Pawnee**

SHOT OR TREATED
CONTRACTOR **H-30, Inc.**



ISSUED

CASING

20 10
15 8-5/8" 561' cemented w/300 sxs cement ELEVATION 2,008 KB

12 6
13 5
4 1/2" 4,054' cemented w/125 sxs cement

PRODUCTION 7,060,000 MOPGD

Cong.

FIGURES INDICATE BOTTOM OF FORMATIONS

Soil and Sand	70'
Sand and Blue Shale	563'
Red Bed and Shale	978'
Anhydrite	1,012'
Shale	1,795'
Shale and Lime	2,120'
Lime and Shale	2,705'
Shale and Lime	3,008'
Lime and Shale	3,540'
Shale	3,610'
Lime	3,840'
Lime and Shale	3,935'
Lime	3,995'
Lime, Shale and Chert	4,025'
Cherty Conglomerate	4,035'
Lime	4,055'
Rotary Total Depth	4,055'

LOG TOPS:

Heebner	3493
Toronto	3511
Brown Lime	3609
Lansing	3618
BKC	3866
Chty Conglomerate	3981
Viola	4008

DST (1) 3941-95
DST (2) 4003-35

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Dean Britting

Dean Britting

State of Kansas

County of Sedgwick

} SS:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 3rd. day of October, 1972.



Elmer Willeson