


KANSAS CORPORATION COMMISSION

Have log

WELL RECORD

26-22-16W

(Mail to Kansas Geological Survey, 4150 Monroe Street, Wichita, Kansas 67209)



Lease Name: Dunbar Well No. 1
 Well Located: SW/4 SW/4 SE/4
SEC 26 TWP 22S RGE 16W
 Operator: Barnett Oil Company
 Address: 411 First Nat'l Bank Bldg., Wichita, Kansas
 Elevation: Ground 2011 D.F. 2013 K.B. 2016
 Type Well: (Oil, gas, dry hole) Gas

Drilling Commenced: Nov. 26, 1971 Drilling Completed: Dec. 12, 1971
 Well Completed: Dec. 27, 1971 Total Depth 4038'
 Initial Production: Gauged 1 1/2 MCFG.

Casing Record

Size: 8 5/8" Set at 235' Size: Set at
 Size: 4 1/2" Set at 4037' Size: Set at

Liner Record

Size: Set from To

Cementing

Casing Size	Sacks	Type Cement and Additives
<u>8 5/8</u>	<u>200</u>	<u>Posmix HA-5</u>
<u>4 1/2</u>	<u>175</u>	<u>60-40 Posmix - salt saturated</u>

Perforations

Formation	Perforated Interval and Number Shots
<u>Conglomerate</u>	<u>3982-88 - 13 shots</u>
<u> </u>	<u> </u>
<u> </u>	<u> </u>
<u> </u>	<u> </u>

Electric Log Run (Show type log and depths covered)

None

30-5500

Show Drill Stem Tests, '26-22-16w
Well Stimulation and
Production Tests

Formation Top Bottom

Sand	0	96
Sand & Shale	96	235
Shale	235	440
Sand	440	509
Shale & Red Bed	509	972
Anhydrite	972	997
Shale & Shells	997	1490
Shale & Lime	1490	3460
Lime	3460	3970
Lime & Chert	3970	3990
Lime	3990	4038
T.D.		4038

DST #1 - 3943-3970 - 30; 30; 30; 30; strong
blow thruout; rec. 15' mud. FP - 27/37;
SIP - 201/201.

DST #2 - 3970-3990 - 30; 30; 60; 45; Strong
blow - 6TS/5"; rec. 20' GCM; gauged 258,000
CFG.

SMP TOPS	DEPTH
HER	2010
WIN	2062
TOW	2128
FT RI	2172
B FLOR	2252
WRE	2282
CO GR	2335
COTTON W	2465
NEVA	2513
FOR	2576
ADM	2620
WAB	2760
LANG	2826
TARK	2892
ELM	2953
HOW	3041



860841