

Company- A. F. BRANN
Farm- Boyd


No. 1

SEC. 4 T. 22 R. 16W
NW SW SW

4-22-16W

Total Depth. 3888'
Comm. 3-21-56 Comp. 5-4-56
Shot or Treated.
Contractor.
Issued. 3-30-57

County Pawnee
KANSAS



2005' KB

Elevation. _____

Production. 199 BOPD

Figures indicate Bottom of Formations.

NO LOG AVAILABLE

All measurements and subsea data are based on Kelly Bushing elevation.

SCHLUMBERGER TOPS

Dakota Sand	
(Scout)	426
Anhydrite (Scout)	980
Heebner	3391
Brown Lime	3500
Lansing	3507
Base/Kansas City	3732
Conglomerate	3830
Simpson Shale	3832
Arbuckle	3838

Zones of Porosity & Staining:

Lansing/Kansas City:
3544-46, 3548-50, 3554-56,
cherty, chalky lime, poor
porosity, stains, tr. free oil.
3594-3604 drab, very porous
lime, no odor, no free oil.
3638-42 drab, light brown,
limestone, no odor.
Arbuckle
3838-50 gray, pink dolomite,
fair porosity, odor, stains,
free oil
3850-60 pink, dolomite,
vugular porosity, good stains,
free oil.
3860-88 pink, light brown,
dolomite, fair to good
porosity, good stains, odor.

DRILL STEM TESTS

DST #1 3540-62, Op. 30 min.
Shut in 15 min. Rec. 25' mud.
BHP 0#.
DST #2 3839-48, Op. 31 min.
Shut in 20 min. Gas in 5 min.
Flowed oil in 31 min. No wtr.
IFP 450#. FFP 825#. BHP 1200#.

Ran Schlumberger log