

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


4-22-164

Company- A. F. BRANN
Farm- Dodge-Matney No. 1
Unit

SEC. 4 T. 22 R. 16W
C S/2 N/2 SW

Total Depth. 3895'
Comm. 4-4-56 Comp. 5-4-56
Shot or Treated.
Contractor.
Issued. 3-30-57

County Pawnee KANSAS



2002' KB

Elevation. _____

Production. 186 BOPD

CASING:

8" @980'
5" @3893'

Figures indicate Bottom of Formations.

NO LOG AVAILABLE

SCHLUMBERGER TOPS
Heebner 3396
Brown Lime 3500
Lansing 3507
Simpson Shale 3829
Arbuckle 3839

All measurements and subsea
data are based on Kelly
Bushing elevation.

Zones of Porosity and Staining:

Arbuckle Section:
3839-46 gray, pink, porous
dolomite, good odor & stains.
3846-51 light brown, porous
cherty dolomite, good odor,
free oil.
3851-61 light brown,
coarsely crystalline
dolomite, oolitic chert.
good odor, free oil.
3861-90 Dolomite as above,
w/stains becoming lighter.

No drill stem tests made.

Ran Schlumberger log