

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


4-22-16W

Company. A. F. BRANN
Farm Dodge-Matney No. 2

SEC. 4 T. 22 R. 16W
SE SW NW

Total Depth. 3900
Comm. 6-9-56 Comp. 6-21-56
Shot or Treated.
Contractor. Musgrove Petroleum Corporation
Issued. 8-18-56

County Pawnee
KANSAS



CASING:

8 5/8 @ 993' w/ 500 sx cmt.
5 1/2 @ 3900' w/ 150 sx cmt.

Elevation. 2013 RB

Production. 103 BOPD

Figures indicate Bottom of Formations.

sand	60
shale	213
shale & shells	430
sand	525
shale & shells	892
anhydrite	992
anhydrite, shale & shells	1570
shale & lime streaks	1830
shale & lime	2530
shale & lime streaks	2845
lime & shale	3760
lime	3815
lime & shale	3857
lime	3900
Total Depth	

TOPS:

Heebner	3402
Brown lime	3506
Lansing	3514
Base KC	3738
Simpson shale	3842
Arbuckle	3850

DST #1: 3851-57, open 25 min. SI 20 min.
very strong bl. rec. gas 9 min. flowed
oil 14 min. BHP 1160#