

Company- KEWANEE OIL CO.
Farm- Stucky No. 1


SEC. 20 T. 22 R. 2W

SE SE SW

330' FSL, 2310' FWL

20-22-2W
County Harvey KANSAS

Total Depth. 3971'
Comm. 11-26-58 Comp. 12-27-58
Shot or Treated.
Contractor. Capitt Drig. & Carter Drig.
Issued. 3-14-59



CASING:
8 5/8" 248.25' cem w/200 sx.
5 1/2" 3745.57' cem w/100 sx.

Elevation. 1426' CM

Production. 17 BOPD

Figures Indicate Bottom of Formations.

surface clay	30
sand	65
shale & shells	250
shale & lime	450
lime & shale	900
shale & lime streaks	1135
shale & lime shells	1460
shale & shells	1715
shale & lime streaks	1945
shale	2040
lime with shale	2105
lime and shale	2450
lime	2590
lime & shale	2680
lime	2805
lime & shale	2940
shale and lime	3045
lime and shale	3145
lime	3198
lime - chert	3270
lime	3305
lime and chert	3388
lime	3409
lime and chert	3471
lime	3509
shale	3536
sand	3542
chert & lime	3564
lime	3573
shale and lime (sandy)	3605
shale and lime	3660
lime	3689
sand	3740
sand and shale	3757
shale	3772
lime	3971 RTD
Total Depth	

TOPS: SCHLUMBERGER
Lansing 2440
Mississippi 3132
Kinderhook 3509
Misener 3536
Hunton 3542
Maquoketa 3589
Viola 3649
Simpson 3692
Arbuckle 3770

Completion: Initial Injection:
Simpson - Natural - Through perforations 3692'-934'
Arbuckle - open hole, 3745.6' - 3971' - Acidized w/5000 gals. 15% HCL
Arbuckle - After Acid - Took 151.30 BW on vacuum in 1 1/4 hrs.

Initial Production: Simpson - Natural - 15.03 BO & 56.78 BW in 7 hours.