

2-22-22W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- PICKRELL DRILLING
Farm- Johnson No. 1

SEC. 2 T. 22 R. 22W
C SW SW

Total Depth. 4560'
Comm. 2-5-64 Comp. 2-10-64
Shot or Treated.
Contractor. Pickrell Drlg.
Issued. 5-23-64

County Hodgeman
KANSAS



Elevation. 2190' RB

CASING:

8 5/8" 271' cem w. 180 sx

Production. DRY

Figures Indicate Bottom of Formations.

sandy clay	60
sandy, shale & shells	160
shale & shells	585
red beds & shale	710
Blaine	725
shale & shells	810
sand	1005
red beds, shells & shale	1355
anhydrite	1395
red, bed, shale & shells	1730
shale	1890
shale, lime	2025
lime, shells, shale	2150
lime	2757
lime, shells, & shale	2875
lime & shale	3638
sandy lime & shale	3720
lime & shale	3865
lime	3988
lime & shale	4060
lime	4150
lime & shale	4390
lime	4418
Mississippian Dolomite	4440
Mississippian Chert	4440
Mississippian	4547
Gilmore City	4560 RTD
Total Depth	

TOPS: SCOUT	
Anhydrite	1363
Heebner	3761
Lansing	3817
Marmaton (S)	4196
Fort Scott	4349
Mississippi Dolomite	4416
Mississippi Osage	4436