

KANSAS

**WELL COMPLETION REPORT AND
DRILLER'S LOG**

IMPORTANT
Kans. Geo. Survey request
samples on this well.

State Geological Survey

API No. 15 — 083 —

County


20,801
WICHITA BRANCH

S. 3 T. 22 R. 22 ¹/₄ W SEP

Loc. C SE NE

County Hodgeman

640 Acres
N



Locate well correctly

Elev.: Gr. 2183

DF KB 2192

Operator

Woolsey Petroleum Corp.

Address

300 West Douglas, Suite 400 Wichita, Kansas 67202

Well No.

#1

Lease Name

M. Salmans

Footage Location

feet from (N) (S) line

feet from (E) (W) line

Principal Contractor

Dunne-Gardner Petroleum, Inc.

Geologist

David L. Kirk

Spud Date

1-18-81

Date Completed

1-28-81

Total Depth

4618'

P.B.T.D.

Directional Deviation

Oil and/or Gas Purchaser

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 $\frac{1}{4}$ "	8-5/8"	24#	580'	HLC & Class A	300	3% CC $\frac{1}{4}$ # Floce1
Production	7-7/8"						

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Pecker set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS		Oil	Gas	Water	Gas-oil ratio
		bbls.	MCF	bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be trans-
mitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation
Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note
Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator WOOLSEY PETROLEUM CORP.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Dry Hole
Well No. 1	Lease Name M. Salmans	
S 3 T 22 R 22 E W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Base Stone Corral	(+ 822')			1370'
Heebner	(-1584')			3776'
Fort Scott	(-2172')			4364'
Mississippi	(-2309')			4501'
DST #1 4366-4388' (Fort Scott)				
30-30-30-30				
1st Op: NB				
2nd Op: NB				
Rec: 10' mud				
IHP 2250#	FFP 18-18#			
IFP 18-18#	FSIP 36#			
ISIP 18#	FHP 2250#	BHT 110°F		
DST #2 4473-4495' (Reworked Miss.)				
45-60-60-120				
1st Op: WB died in 10"				
2nd Op: NB				
Rec: 60' mud				
IHP 2259#	FFP 54-54#			
IFP 18-27#	FSIP 1237#			
ISIP 1200#	FHP 2259#			
DST #3 4503-4521' (Miss. Osage)				
30-60-45-90				
1st Op: SB				
2nd Op: SB				
Rec: 1860' SW				
IHP 2268#	FFP 492-751#			
IFP 125-447#	FSIP 1390#			
ISIP 1399#	FHP 2231#	BHT 118°F		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	 Ronald J. Miller Operations Manager March 3, 1981
	Signature Title Date