

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas


5-22-22W

Company- SUNRAY MID-CONTINENT OIL CO.
 Farm- E. Barnett No. 1

SEC. 5 T. 22 R. 22W
 C SE SW

Total Depth. 4600'
 Comm. 4-28-62 Comp. 5-13-62
 Shot or Treated.
 Contractor. Garvey Drilling Co.
 Issued. 9-29-62

County Hodgeman
 KANSAS



Elevation. 2231' DE

Production. TEMP ABND

CASING:

8 5/8" 266' cem w/200 sx.
 5 1/2" 4599' cem w/100 sx.

Figures Indicate Bottom of Formations.

| | |
|--------------------------|------|
| surface soil & post rock | 40 |
| shale & sand | 266 |
| shale | 340 |
| shale & red bed | 819 |
| Blaine anhydrite | 831 |
| shale & sand | 1360 |
| shale | 1445 |
| anhydrite | 1475 |
| shale & lime | 1715 |
| shale & shells | 2036 |
| shale | 2330 |
| lime | 2730 |
| shale & lime | 3566 |
| shale | 3855 |
| shale & lime | 3961 |
| lime | 4149 |
| lime & shale | 4303 |
| lime | 4364 |
| lime & shale | 4509 |
| lime | 4600 |
| Total Depth | |

TOPS: LOG

| | |
|--------------|------|
| Stone Corral | 1445 |
| Heebner | 3832 |
| Lansing | 3889 |
| Marraton | 4262 |
| Cherokee | 4410 |
| Mississippi | 4513 |