

5-22-22W
V


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SOCONY MOBIL OIL., INC.
Farm- Wayne A. Salmans No. 1

SEC. 5 T. 22 R. 22W
C SW SE

Total Depth. 4610'
Comm. 3-14-62 Comp. 3-31-62
Shot or Treated.
Contractor. Barnett Drilling, Inc.
Issued. 8-11-62

County Hodgeman
KANSAS



Elevation. 2296' DF (CC)

Production. 155 BO/83 BW

CASING:

8 5/8" @ 248' w/200 sks.
5 1/2" @ 4609' w/150 sks.

Figures indicate Bottom of Formations.

post rock & clay	125
sand & clay	165
shale	606
shale & red bed	926
sand	1116
shale & shells	1156
shale, shells & red bed	1280
lime & sand	1320
shale & shells	1465
Anhydrite	1500
shale	2275
shale & lime	2440
lime & shale	3945
lime	4550
lime & chert	4575
Miss. lime & chert	4610
TOTAL DEPTH	4610

TOPS: SCOUT

Heebner	3893
Lansing	3910
Kansas City	4075
Marmaton	4284
Ft. Scott	4370
Cherokee	4434
Mississippi	4523