

6-22-22W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- IMPERIAL OIL CO.  
Farm- Barnett No. 3

SEC. 6 T. 22 R. 22W  
C SW SE

Total Depth. 4555'  
Comm. 6-20-62 Comp. 7-4-62  
Shot or Treated.  
Contractor.  
Issued. 9-29-62

County Hodgeman  
KANSAS



CASING:  
8 5/8" 253' cem w/175 sx.

Elevation. 2295' KB

Production. Dry

Figures indicate Bottom of Formations.

post rock	50
shale	515
shale & sand	843
anhydrite	856
shale & red bed	1470
shale & shells	1870
shale & lime	2230
lime	2810
lime & shale	3932
lime	4228
lime & shale	4238
lime	4470
lime & chert	4546
lime	4555 RTD
Total Depth	

TOPS:

Heebner	3855
Lansing	3934
Base Kansas City	4246
Cherokee Shale	4430
Mississippi (Osage)	4544

DST #1 4496-4534' op 30 min. Rec. 5' of drilling mud. IBHP 105#, IF 38#, FF 38#, FBHP 30#/20 min.

DST #2 4496-4546' op 30 min. Rec. 5' of drilling mud. IBHP 250#, IF 48#, FF 48#, FBHP 57#/20 min.

DST #3 4497-4550' op 30 min. Rec. 90' of drilling mud. (Tool was slid 6' to bottom when the tool opened) IBHP 1123#, IF 86#, FF 86#, FBHP 1074#/20 min.

DST #4 4548-4555' op 1 hr. Rec. 1410' of very slightly oil & gas cut salt water. IBHP 1360#, IF 153#, FF 626#, FBHP 1310#/20 min.